BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2023-24/OW/WORK_INDENT2521

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/16/2023-24, Date: 02-02-2024

Name Of Work: Maintenance of water supply works to existing borewells at Dasarahalli village surrounding area in ward no. 08 (Amrutahalli).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of G Prudvi	
				In Figures	In Words
1	20.00	The lifting of submersible pumpset from well.	Each	1339.26	Rupees One Thousand Three Hundred Thirty Nine and Twenty Six Paise Only
2	10.00	The Transportation of pumping machineries	Each	1071.40	Rupees One Thousand Seventy One and Forty Paise Only
3	1.00	Rewinding of submersible pumpset with copper winding wires of appropriate guage, as per specifications and / or directions of the departmental officials, including all materials, labour, equipment and testing. for all types of submersible pumpsets etc.(with guarantee period not less than 6 months) For all types of submersible pumpsets above 7.0 HP and upto 7.5H.P.	Each	3427.61	Rupees Three Thousand Four Hundred Twenty Seven and Sixty One Paise Only
4	5.00	For all types of submersible pumpsets above 10 HP and upto 11 H.P.	Each	4604.38	Rupees Four Thousand Six Hundred Four and Thirty Eight Paise Only
5	10.00	For all types of submersible pumpsets above 12 HP and upto 13 H.P.	Each	5000.00	Rupees Five Thousand Only
6	10.00	For all types of submersible pumpsets 15HP to 20 HP	Each	7700.81	Rupees Seven Thousand Seven Hundred and Eighty One Paise Only
7	15.00	The bowls of same type and make .	Each	1339.26	Rupees One Thousand Three Hundred Thirty Nine and Twenty Six Paise Only
8	5.00	The Intermediate piece (IP) with IP leaded bronze brush.	Each	937.48	Rupees Nine Hundred Thirty Seven and Forty Eight Paise Only
9	10.00	The upper flange	Each	580.34	Rupees Five Hundred Eighty and Thirty Four Paise Only
10	5.00	Upper/ Lower Housing	Each	1071.40	Rupees One Thousand Seventy One and Forty Paise Only
11	10.00	The Guide Vane	Each	698.00	Rupees Six Hundred Ninety Eight Only
12	5.00	The Impeller (Shell moulded with aluminium and bronze.)	Each	1339.26	Rupees One Thousand Three Hundred Thirty Nine and Twenty Six Paise Only
13	5.00	The discharge outlet (DO) bearing DO steel brush DO bearing.	Each	1830.32	Rupees One Thousand Eight Hundred Thirty and Thirty Two Paise Only
14	5.00	The pump shaft made out of stainless steel counterless ground with key way (upto 8 stages).	Each	1339.26	Rupees One Thousand Three Hundred Thirty Nine and Twenty Six Paise Only
15	10.00	Pump Couping (Stainless Steel)	Each	1339.26	Rupees One Thousand Three Hundred Thirty Nine and Twenty Six Paise Only
16	5.00	Stud and Nuts	Each	178.56	Rupees One Hundred Seventy Eight and Fifty Six Paise Only
17	10.00	Motor Base With Pin	Each	446.42	Rupees Four Hundred Forty Six and Forty Two Paise Only

Signature of Contractor

Executive Engineer

Name Of Work: Maintenance of water supply works to existing borewells at Dasarahalli village surrounding area in ward no. 08 (Amrutahalli).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of G Prudvi	
				In Figures	In Words
18	5.00	The Starter of Motor up to 4 to 5 HP	Each	3124.94	Rupees Three Thousand One Hundred Twenty Four and Ninety Four Paise Only
19	5.00	The Rotor of Motor up to 4 to 5 HP	Each	1785.68	Rupees One Thousand Seven Hundred Eighty Five and Sixty Eight Paise Only
20	10.00	Carbon Housing	Each	178.56	Rupees One Hundred Seventy Eight and Fifty Six Paise Only
21	10.00	The Carbon Housing (Thrust bearing block assembly complete with segment bearing pad.	Each	1964.25	Rupees One Thousand Nine Hundred Sixty Four and Twenty Five Paise Only
22	5.00	Oil Seal Steel Bush	Each	223.21	Rupees Two Hundred Twenty Three and Twenty One Paise Only
23	10.00	Oil Seal	Each	312.49	Rupees Three Hundred Twelve and Forty Nine Paise Only
24	5.00	The steel bearing bush (DO steel bush)	Each	357.13	Rupees Three Hundred Fifty Seven and Thirteen Paise Only
25	5.00	Allen Screw	Each	1071.40	Rupees One Thousand Seventy One and Forty Paise Only
26	10.00	The pump key (stainless steel)	Each	580.34	Rupees Five Hundred Eighty and Thirty Four Paise Only
27	7.00	Non return valve (NRV) assembly complete with rubber O Ring	Each	580.34	Rupees Five Hundred Eighty and Thirty Four Paise Only
28	10.00	Cable Guard	Each	312.49	Rupees Three Hundred Twelve and Forty Nine Paise Only
29	5.00	Strainer	Each	401.77	Rupees Four Hundred One and Seventy Seven Paise Only
30	10.00	Brass Filter	Each	937.48	Rupees Nine Hundred Thirty Seven and Forty Eight Paise Only
31	5.00	Re-erection charges of pumping machineries including overhauling and pointing	Each	1785.68	Rupees One Thousand Seven Hundred Eighty Five and Sixty Eight Paise Only
32	10.00	Lock Ring	Each	312.49	Rupees Three Hundred Twelve and Forty Nine Paise Only
33	10.00	The Carbon Housing (Top carbond / ferrodo padding)	Each	312.49	Rupees Three Hundred Twelve and Forty Nine Paise Only
34	10.00	The Gun Metal bearing, centrifugally cast Aluminium Bronze bearing bush	Each	758.91	Rupees Seven Hundred Fifty Eight and Ninety One Paise Only
35	9.00	Circillps	Each	178.56	Rupees One Hundred Seventy Eight and Fifty Six Paise Only
36	15.00	Supplying & fixing of Porcelain fuse channel with cut out onexisting wooden/panel using necessary nuts, bolts and washers complete	Each	358.02	Rupees Three Hundred Fifty Eight and Two Paise Only
37	150.00	Cutting and threading G.I. pipes for pump fitting, public fountains with appurtenances., where the length of pipe laid is less than 6 metre Pipes of dia 32mm to 80mm	Each	280.00	Rupees Two Hundred Eighty Only

Signature of Contractor

Executive Engineer

Name Of Work: Maintenance of water supply works to existing borewells at Dasarahalli village surrounding area in ward no. 08 (Amrutahalli).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. Anurah Enterprises, Prop. Rahul Gowda N A	
				In Figures	In Words
38	50.00	Supply and delivery at site Brand new best make PVC insulated cable of Flat 3 core (sheathed) of nominal cross sectional area as per IS 694-1990 with ISI Mark and as per its latest amendments. 1x3x6 m2	Mtr	165.17	Rupees One Hundred Sixty Five and Seventeen Paise Only
39	5.00	Supply and delivery at site delivery of best indigenous brand new MCB (Miniature Circuit Breakers) of required capacity as per IS 88228/1978 and its latest amendments and with ISI Mark of 6/10/16/20/25/40 Amps with scalable box.	Per Pole	1026.76	Rupees One Thousand Twenty Six and Seventy Six Paise Only
40	6.75	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means above 600 mm trench width as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & boning rods at every 100 mm whevere necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. Depth exceeding 1.5 m, but not exceeding 3 m.	Cum	325.08	Rupees Three Hundred Twenty Five and Eight Paise Only
41	20.00	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete.	Mtr	104.46	Rupees One Hundred Four and Forty Six Paise Only
42	6.75	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. ncluding cost of all labour complete as per specifications.	Cum	142.85	Rupees One Hundred Forty Two and Eighty Five Paise Only

Signature of the Contractor

Executive Engineer
Byaraynapura Division
Bruhat Bengaluru Mahanagara Palike